

Statutory Requirements for Modular Integrated Construction Projects

www.cic.hk October 2023

AMENDMENT NO. 1/2023

Revised Chapters 3, 4, 5, 6 and 7 for Reference Material on the Statutory Requirements for Modular Integrated Construction Projects (September 2020)

Chapter	Department	New/Revised Documents, Guidelines, etc. on MiC Issued by the Respective Department Since September 2020	Amendments Made in the Revised Chapters
3	Buildings Department	The following documents have been revised/issued: (a) PNAP ADV-36 MiC (Apr 2022); (b) BD, LandsD & PlanD JPN No. 2 Second Package of Incentives to Promote Green and Innovative Buildings (July 2022); (a) BD, LandsD & PlanD JPN No. 8 Incentive to Promote Green and Innovative Buildings - Enhanced Facilitation Measures for Buildings Adopting Modular Integrated Construction (July 2022)	The following revisions have been made: (a) Approval of plans for MiC project was clarified in Section 3.3. (b) The enhanced/alternative arrangements for qualified supervision and quality audit for MiC as promulgated in Appendix B to PNAP ADV-36, including provision of quality audit checks arrangement by videotelephony, was updated in Section 3.4. A figure showing the critical stages of IPA application and plan submissions for MiC project was included. (c) The enhanced facilitation measures for buildings adopting MiC including increasing the concession of gross floor area and providing corresponding site coverage concession as well as supporting applications for exceeding building height limits as promulgated in JPN No. 8 were updated in Section 3.5. An example of GFA concession calulations was included.
4	Fire Services Department	The following document has been issued: (a) FSD Circular Letter No. 3/2020 - Facilitation Measures of Application for Approval of Portable Equipment and Acceptance of Fire Service Installations and Equipment (FSIs) and Fire Safety Products (Jul 2020).	Section 4.4 on Acceptance Inpection was revised to give more details on the revised application procedure for inspection and testing of fire service installations and equipment by FSI/501 submission.
5	Water Supplies Department	The following documents have been issued: (a) Guide to Application for Water Supply (December 2021 version); and	Section 5.4 on Final Inspection at Building Site and Commissioning Requirements and Section 5.5 on Effect of Water Supply were updated.


		(b) Technical Requirements for Plumbing Works in Buildings (December 2021 version).	
6	Electrical and Mechanical Services Department	The following documents have been issued: (a) Code of Practice for the Electricity (Wiring) Regulations (2020 Edition) (see Code 26T on Installation of MiC) (2020); (b) Code of Practice on Energy Labelling of Products (Dec 2020); and (c) Guideline on Submission of Product Information (Jun 2022).	Section 6.2 on Fixed Electrical Installations and Section 6.5 on Gas Supply Installations were updated.
7	Transport Department	The following documents have been issued: (a) Form TD 290 - Application for "Long Load" and "Wide Load" Permits; and (b) Guidelines on Application for Long/Wide Load Permit (July 2022).	Section 7.2 on Wide Load Permit was updated.


with the principles and guidelines given in PNAP ADM-19. The plans will be handled under the centralised processing system as stipulated in PNAP ADM-2, through which all interested government departments will be consulted and their comments will be collated by BD.

For a project adopting MiC system on the IPA list, re-assessment of the proposed MiC system in respect of the various performance aspects that have been pre-accepted will not be necessary unless alterative design and materials/construction methods, which deviate materially from the pre-accepted MiC system, component or testing criteria of the accepted test reports, are proposed.

For a project adopting MiC system not on the IPA list, AP and RSE should submit essential information as listed in PNAP ADV-36 to BD for consideration of the performance and technical aspects of the proposed MiC system as mentioned in Section 3.2. While IPA is not a pre-requisite for the approval of plans, any MiC details not yet available at the plan submissions may be submitted later for BD's acceptance prior to factory production.

Critical stages of IPA application and plan submissions for MiC project are illustrated in Figure 3.1.





JPN No. 1: Green and Innovative Buildings (BD, LandsD & PlanD, 2019)

JPN No. 2: Second Package of Incentives to Promote Green and Innovative Buildings (BD, LandsD & PlanD, 2022)

JPN No. 8: Incentive to Promote Green and Innovative Buildings Enhanced Facilitation Measures for Buildings Adopting Modular Integrated Construction (BD, LandsD & PlanD, 2022)

Figure 3.2 – Example of GFA Concession Calculations

	Table 8.1 – C	ontacts of Re	egional Offices	of EPD ⁵⁴	
Office/ Regional Offices	Address	Telephone	Fax Number	Email Address	Control Districts
Regional Office	5/F., Nan Fung Commercial Centre, 19 Lam Lok Street, Kowloon Bay, Kowloon.	2755 5518	2756 8588	hotline_e@epd.gov.hk	Kwun Tong, Wong Tai Sin, Sai Kung and Kowloon City
(East)	8/F., Cheung Sha Wan Government Offices, 303 Cheung Sha Wan Road, Kowloon.	2402 5200	2402 8272	hotline_e@epd.gov.hk	Yau Tsim Mong
Regional Office (South)	2/F, Chinachem Exchange Square, 1 Hoi Wan Street, Quarry Bay, Hong Kong.	2516 1718	2960 1760	hotline_s@epd.gov.hk	Hong Kong Island and Islands
Regional Office (West)	8/F, Tsuen Wan Government Offices, 38 Sai Lau Kok Road, Tsuen Wan, New Territories.	2417 6116	2411 3073	hotline_w@epd.gov.hk	Tuen Mun, Tsuen Wan, Kwai Tsing and Sham Shui Po
Regional Office (North)	10/F, Sha Tin Government Offices, 1 Sheung Wo Che Road, Sha Tin, New Territories.	2158 5757	2685 1133	hotline_n@epd.gov.hk	Yuen Long, Sha Tin, Tai Po and North

_

 $^{^{54}\} https://www.epd.gov.hk/epd/english/application_for_licences/sub_applic/application_maincontent 38.html$

furnish manifests in respect of the cargoes being imported or exported if they are requested to do so.




Figure 9.1 – Locations of Land Boundary Control Points, Kwai Tsing Container Terminal, mid-stream sites, River Trade Terminal and Public Cargo Working Areas (https://www.hkmpb.gov.hk/en/port.html)

<u>APPENDIX B - WORKFLOW FOR SUBMISSION AND APPROVAL OF PLANS TO BUILDINGS DEPARTMENT AND ADDITIONAL REQUIREMENTS FOR MIC</u>

		AP/RSE
Submission and Approval of	AP/RSE (a) submit GBP, superstructure plans, etc., to BD for approval.	(a) demonstrate proposed MiC system in compliance with BO and its subsidiary regulations (Quote IPA reference no. of the pre-accepted MiC system on plans or submit essential information stipulated in PNAP ADV-36 to BD for consideration)
Plans before Commencement of Module Production	BD (a) process GBP, superstructure plans, etc; and. (b) provide decision within 60 days.	AP/RSE/RGBC (a) submit Quality Assurance Scheme and MiC Supervision Plan in accordance with the imposed approval conditions at least 14 days before commencement of the production work in the MiC factory; and (b) notify BD in writing if opting for alternative on-site audit check.
Module		AP/RSE/Quality Control Supervisory Team (a) conduct regular supervision (AP and RSE-monthly and T3*-weekly); (b) supervise module production in respect of fire resisting construction, drainage works, structures, etc.; and (c) keep records of production, inspection, auditing and testing of modules (T3*) in a log book, with a copy kept at building site office for BD inspection when required.
Production at MiC Factory		Authorized Signatory of RGBC / Quality Control Co-ordination Team (a) conduct regular supervision (AS-monthly, T3*-weekly and T1*- continuous); (b) supervise module production; and (c) keep records of production, inspection, auditing and testing of modules (T3*/T1*) in a log book, with a copy kept at building site office for BD inspection when required.
	AP/RSE (a) apply for consent to commence superstructure works. BD (a) process consent application; and (b) provide decision within 28 days.	AP/RSE/RGBC (a) notify BD not less than 7 days before commencement of site works; (b) supervise site installation works; (c) submit a copy of the AP, RSE and RGBC's audit reports on the MiC factory; and (d) submit structural material certificates/test reports in accordance with the imposed approval conditions.
Construction at Building Site		AP/RSE If opting for alternative on-site audit check: (a) submit on-site audit report on the quality of the MiC elements delivered to the building site; and (b) submit HOKLAS-endorsed certificates for concrete/tensile strength testing within 60 days of the delivery of the modular units.
Completion	AP/RSE/RGBC (a) certify completion of building works in accordance with the BO and its subsidiary regulations and the approved plans; and (b) Submit record plans and schedule of building materials and products in accordance with PNAP APP-13.	
Completion Certification	BD (a) process occupation permit application; and (b) provide decision within 14 days.	
	* T3/T1 refers to Grade T3/T1 Technically Com Practice for Site Supervision	upetent Person equivalent as stipulated in the Code of

<u>APPENDIX C - WORKFLOW FOR SUBMISSION AND APPROVAL OF PLANS TO FIRE SERVICES DEPARTMENT AND ADDITIONAL REQUIREMENTS FOR MIC</u>

Project Stage Submission and Approval of Plans Additional Requirements for MiC (a) Provide adequate access points, inspection pits or accessible Submit application (Form FSI/314) together with two sets recesses for covered-up installations for inspection, testing and of FSI plans, and a copy of Fire Service Notes in the relevant approved building plans (and highlighting in the future maintenance. covering letter that MiC will be used) to BD for referral to (b) Design flexible pipe jointing between modules, where FSD for approval. required, for services connection, (c) Consider cabling facilities for FSI between modules for on-Submission and site installations of power and control cables. **Approval of Plans** (d) Use FSI equipment and materials accompanied with product (a) Process FSI plans. listing certificates/records/letters issued by the respective before (b) Provide decision within 20 working days. product certification bodies accepted/approved in accordance Commencement (c) Issue standard letter or a Fire Service Certificate (FS with FSD Circular Letter No. 1/2007. 161), if approved, and return one set of the endorsed plans of Module to AP/RFSIC. **Production** (a) Submit design of pressurization of staircase, ventilation/air conditioning control system and smoke extraction, if applicable. (a) Conduct regular supervision in the module production process to ensure that the equipment and materials used in FSI are in full compliance with the relevant statutory requirements. Module (b) Keep an inspection log book, including names and registration numbers (FSD/RC No.) of the RFSIC responsible for conducting the Production at quality assurance supervision, and details of the inspection. auditing and testing of the off-site FSI works at the MiC factory, **MiC Factory** and provide the log book to FSD when required. RFSIC is advised to (a) Check and inspect the FSI installed in the integrated modules, after they are delivered to site and before the on-site assembling process, especially if there is concern over possible damage during transit and difficulty in replacing/repairing the installed FSI Construction after assembly. at Building Site (b) Monitor the on-site construction works to ensure proper fixing of the FSI elements Submit application (FSI/501) and certificate of completion (FSI/501a) to FSD for acceptance inspection, including Form FSI/314, and 2 sets of as-fitted FSI layout plans, a schedule of the submitted FSI layout plans, testing and commissioning checklists, and a FSIs equipment list. (a) Carry out acceptance inspection within 15 working days after receipt of the application. Compliance (b) Issue Form FS 172 for non-government buildings, or acceptance memo/letter for government buildings after Certification confirming that the installed FSI are in full compliance with the FS requirements. (c) Inspect the ventilation system to certify compliance, where applicable.

Note: Reference should be made to FSD Circular Letter No. 3/2019 - Guidance Notes on Submission, Approval and Acceptance Inspection of Fire Service Installations and Equipment in Modular Integrated Construction Building Projects and FSD Circular No. 1/2020 - Revised Application Procedure for Inspection and Testing of Fire Service Installations and Equipment in New Building.

<u>APPENDIX D1 - WORKFLOW FOR SUBMISSION AND APPROVAL OF PLANS TO WATER</u> SUPPLIES DEPARTMENT AND ADDITIONAL REQUIREMENTS FOR MIC

Additional Requirements for MiC Submission and Approval of Plans **Project Stage** Submit the following: Submit application (Form WWO 542) together with a (i) a section clearly specifying the part of the plumbing installations plumbing proposal to WSD for approval. to be constructed in the MiC factory; and a Vertical Plumbing Line Diagram and/or other documents as appropriate showing the extent of the plumbing installations; and (ii) a supervision plan of the construction of the plumbing installations at the MiC factory for agreement by WSD. Issue approval letter for Form WWO 542 and demand Submission and note. **Approval of Plans** AP/Consultant before AP, LP and Applicant Submit the following if there are parts of plumbing installations to Submit Form WWO46 Parts I & II to WSD to seek Commencement be covered up in the MiC factory, in such a manner that they cannot permission for commencement of plumbing works at be exposed for inspection and non-destructive tests at the building of Module building site. **Production** (i) shop drawings showing details of the plumbing installations in the modules that will be covered up in the MiC factory; and (ii) production schedule of the modules, in particular the production schedule of the plumbing works and the corresponding inspection schedule for the plumbing works to be covered up in the modules in the MiC factory. LP, RPW, MiC Supplier Issue Form WWO46 Part III to grant permission for (a) Implement the supervision plan as agreed by WSD. commencement of plumbing works at building site. (b) Keep supervision records and produce to WSD for inspection when required. (c) Declare (by LP) on the supervision records any supervision carried out in the MiC factory. (d) Coordinate and liaise (by LP) with the WSD's Inspection Agent regarding the exact inspection dates of the plumbing installations to the covered up at the MiC factory. Module WSD's Inspection Agent Production at Carry out interim inspection of the concealed parts of the plumbing installations at the MiC factory before they are covered up, to **MiC Factory** ensure compliance with WWO/WWR. LP or His/Her Representative Be present at all interim inspections carried out by the WSD's Inspection Agent. Submit Form WWO 46 Part IV upon completion of whole plumbing works of the MiC project for final inspection. Construction Carry out final inspection for completed plumbing at Building Site Inform LP to provide water supply on site and issue Grant approval of the completed works (issuance of Form WWO 46 Form WWO 46 Part V to LP and applicant. Part V(a)) subject to: (i) satisfactory results of the final inspection by WSD at the building site: (ii) satisfactory results of the interim inspections by the WSD's Inspection Agent of the concealed parts of the plumbing works before they are covered up in the MiC factory; and Certification (iii) compliance with the commissioning requirements specified by WSD.

Note: Reference should be made to Sections 3.12, 4.1.3, 4.2A, 4.3.2A and 4.3.3A and Appendices 2 and 26 of the WSD's Guide to Application for Water Supply (December 2021 version) (https://www.wsd.gov.hk/filemanager/en/content_1805/Guide%20to%20Application%20for%20Water%2 0Supply%20-%202021_Final.pdf)

Idress of MiC factory: SD Reference No. (CCID/ASN): riod of supervision of construction at MiC factory: / / to / / Registered Plumbing Workers (RPW) Supervision Record:	ONSTRUCTED AT OFF	SIIE WIE THE ORT			
Name of RPW Registration no. Date Start Time End Time	roject Name: ddress of MiC factory:				
Name of RPW Registration no. Date Start Time End Time	SD Reference No. (CCI	D/ASN):			
Name of RPW Registration no. Date Start Time End Time	eriod of supervision of co	onstruction at MiC factor	y: / /	to	/ /
Name of RPW Registration no. Date Start Time End Time Signature(s) of RPW Date Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: LP No.: Date Start Time End Time Acclare that plumbing works carried out in the MiC factory mentioned above du MM/YY to DD/MM/YY have been supervised according to the supervision plan accepted by the Whority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a					
Signature(s) of RPW Date Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: LP No.: Date Start Time End Time	Registered Plumbing	<u>workers (RPW) Superv</u>	<u> 1810n Recor</u>	<u>a:</u>	
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time	Name of RPW	Registration no.	Date	Start Time	End Time
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time					
Licensed Plumbers (LP) Supervision and Inspection Record: me of responsible LP: Date Start Time End Time	Signature(s) o	f RPW		Г) ate
			andian Dage		
Date Start Time End Time		AP) Supervision and Insp	<u>becuon Reco</u>		
, declare that plumbing works carried out in the MiC factory mentioned above du/MM/YY_ to DD/MM/YY_ have been supervised according to the supervision plan accepted by the Whority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a					
/MM/YY to DD/MM/YY have been supervised according to the supervision plan accepted by the W hority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a	Date	Start Time		End 7	Гіте
/MM/YY to DD/MM/YY have been supervised according to the supervision plan accepted by the W hority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a					
/MM/YY to DD/MM/YY have been supervised according to the supervision plan accepted by the W hority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a					
/MM/YY to DD/MM/YY have been supervised according to the supervision plan accepted by the W hority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a					
/MM/YY to DD/MM/YY have been supervised according to the supervision plan accepted by the W hority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a					
/MM/YY to DD/MM/YY have been supervised according to the supervision plan accepted by the W hority under the CCID/ASN No. mentioned above. The supervision and inspection are carried out a	dec	are that plumbing works ca	rried out in th	e MiC factory ment	ioned above dur
•	<u>/MM/YY</u> to <u>DD/MM/Y</u>	Y have been supervised acc	cording to the	supervision plan acc	cepted by the Wa
e and time as detailed in this record form.	•		The supervision	on and inspection ar	e carried out at
	z and time as detailed in th	ns record form.			

Note: This form is taken from Appendix 26 of the Guide to Application for Water Supply (December 2021 version) (WSD, 2021)

<u>APPENDIX E2 - WORKFLOW FOR SUBMISSION AND APPROVAL OF PLANS TO ELECTRICITY SUPPLIER AND ADDITIONAL REQUIREMENTS FOR MIC</u>

Project Stage Submission and Approval of Plans Additional Requirements for MiC Submit details of proposed project with a location plan of the project, proposed use of the project, floor plan, proposed transformer room layout (if provided), loading information, standard load estimation information, etc., to the Electricity Submission and Supplier for determination of the proposed arrangement and **Approval of Plans** requirements for providing supply to the new building. before **Electricity Supplier** Inform the AP/Consultant about the requirements for providing supply, including the transformer layout requirements if erection of a new transformer room is of Module **Production** required, after determining the supply arrangement for the new building. REC/REW Submit duly-signed electrical schematic wiring diagram. Return the necessary undertaking letters or other document as described in the requirements of supply provision to the Electricity Supplier, if required. Submit formal application form for each electrical installation to the Electricity Supplier and pay required service charge and deposit (if applicable). REC/REW Carry out insulation resistance (megger) test and other tests as stipulated in the Code of Practice for the Electricity (Wiring) Regulations issued by EMSD on wiring works for pre-wired Module (Note: A Megger test is a method of testing using an **Production at** insulation tester resistance meter to verify the condition of an electrical insulation.) **MiC Factory** AP/Consultant Construct and hand-over the necessary facilities, including new transformer room if required, to the Electricity Supplier **Electricity Supplier** Construction Carry out site work to provide electricity supply to the new at Building Site building. REC/REW After completion of the electrical installation, issue a Work Completion Certificate (Form WR1) and arrange installation inspection with the Electricity Supplier. Electricity Supplier Certification Install meters and connect the supply to the public supply installation and flats, after satisfactory installation inspection.

of delivery should be assessed. A summary of the findings for the hour with the heaviest traffic flow that should be presented is as given in Table 1. As shown in the table, the potential problematic link is Link L29. Link L29 has a V/C ratio of 1.16 for the hour of delivery with the heaviest traffic flow. This implies that there will be congestion along Link 29 for the hour of delivery examined but the congestion is manageable.

Table 1 - Link Capacity Analysis									
Link	Road Name (Example)	Direction	Capacity	Existing Traff	fic Conditions				
Index			(pcu/hr)			with Module Delivery			
				Flow (pcu/hr)	V/C	Flow (pcu/hr)	V/C		
L1	Lung Cheung Rd between Kwun Ton Rd and Clear Water Bay Rd	N/B	6400	2088	0.33	2456	0.38		
L29	New Clear Water Bay Rd near Shun Lee Tsuen Rd	W/B	1800	1315	0.73	2081	1.16		
Note:	The flow is for the hour with the heaviest traffic flow as obtained from the traffic count.								
Legend:	pcu/hr = passenger car unit/hr								

3.5.2 <u>Junction Capacity Analysis</u>

- (a) <u>Junction types</u>. There are three types of junctions: signal-controlled junctions⁶³, priority junctions⁶⁴ and roundabouts⁶⁵.
- (b) Reserve Capacity (RC) (in %). For signal-controlled junctions, RC is used to evaluate the capacity of these junctions. The method of calculation can be found in Section 2.4 of TPDM Vol. 4. A positive RC figure indicates that the junction is operating with spare capacity, and *a negative RC figure indicates that the junction is overloaded*, resulting in traffic queues and longer travelling time.
- (c) <u>Design Flow to Capacity (DFC) ratio</u>. For priority junctions and roundabouts, the DFC ratio is used to evaluate the capacity of these junctions. The DFC ratio compares the design flow to capacity of the junctions. The methods of calculation of the design flow and capacity can be found in Section 4.2.4, and Appendices 1 and 2 of TPDM Vol. 2 respectively. A DFC ratio of 0.85 indicates the junction has a reasonable capacity which would prevent queueing in the majority (85%) of cases. A DFC ratio of 0.7 indicates that queueing would theoretically be avoided in nearly all (95%) of cases at the junction. A DFC ratio greater than 1.0 indicates that the junction is overloaded.
- (d) <u>Presentation method</u>. The capacity of the key junctions along the route for existing traffic conditions and forecast traffic conditions with module delivery during the selected hours of delivery should be assessed. A summary of the findings for the hour with the heaviest traffic flow that should be presented is as given in Table 2. As shown in the table, the potential problematic junctions are Junctions 11 and 21. Junction 11

⁶³ Signal-controlled junctions operate on a time sharing basis. Traffic streams are allowed to enter the junction for a period of time, indicated by an illuminated signals, and during which period conflicting traffic streams are halted.

⁶⁴ Priority junctions operate on the basis that traffic on the major road has continual priority over the traffic on the minor

road. Minor road traffic is controlled by "stop" and "give way" signs and associated carriageway marking.

⁶⁵ Roundabouts could be considered as a form of channelized priority junction. Vehicles enter a one way carriageway and move in a clockwise direction around a central island. Entering vehicles give priority to those vehicles already circulating across their entry.

Annex A – Suggested Project Arrangement for MiC Projects

Project Planning Engage traffic consultant to Seek comments /in-Stage carry out SPA, TIA, TTM & principle approval from CP TD **Tender Stage** Include logistics conditions in tender **Construction Stage** Engage traffic consultant if Engage logistics companies to apply for WLP, based on necessary to revise SPA, the in-principle approval TIA, TTM & CP, if there given by TD are changes in conditions

Annex B – No. of WLPs Issued (as of 31.3.2023)

In Terms of	Туре		No. of WLPs Issued in							
		2018	2019	2020	2021	2022	2023 (up to 31.3.23)			
Type of Vehicle	Medium goods vehicle	438	525	683	677	694	152	580		
	Heavy goods vehicle	234	250	291	318	348	83	294		
Registered Owner	Individual		100	135	144	157	27	110		
	Business		675	839	851	885	208	764		

Annex C – General Requirements for Delivery of Wide Load in Hong Kong

	Routine	Case by Case	Case by Case			
	Overall Width	2.5m <overall td="" width≤3m<=""><td>Overall>3m</td></overall>	Overall>3m			
	≤2.5m					
WLP Required	No	Yes	Yes			
TIA, TTM, SPA & CP	No	Yes	Yes (with more careful			
Required			consideration of the			
			traffic implications and			
			proposal of more			
			sophisticated TTM			
			schemes)			
Time of Delivery	No time restriction	The permitted hours of delivery will depend on the				
		selected route, traffic flows, road conditions, etc., and				
		the results of the TI	A acceptable to TD			
Self-arranged Escort	No	Yes				
(Notes 1 and 2)						
Police Escort (Note 1)	No	N	o			
Notes: 1. Self-arrange	ed escort is the practice re	ecommended by the police. T	There are however situations			
where polic	where police escort may be needed, for example, when the delivery crashes with a VIP convo					
on the day,	, there is an accident alo	ong the route, etc. Under the	ne above-mentioned special			
situations, t	here is no charge for the p	police escort provided.				
2. Reference of	can be made to Section 5.	9 of the CoP for the Loading	of Vehicles (TD, 2019) on			

$\label{eq:local_equation} \textbf{Annex D-Contacts of the Operators of Eastern Harbour Crossing} \ \ \textbf{and Western Harbour Crossing}$

the duties of escort vehicles.

Tunnel	Operator	Telephone	Fax Number
Eastern Harbour Crossing (EHC)	ur Crossing (EHC) Pacific Infrastructure		2347 5037
	Ltd.	2348 0011	
Western Harbour Crossing	Western Harbour	2302 5760/	2781 1729
(WHC)	Tunnel Co. Ltd.	2302 5888	



Feedback Form

Statutory Requirements for Modular Integrated Construction Projects (October 2023)

Thank you for reading this publication. To help us improve our future versions, we would appreciate your suggestions/feedback on the publication.

(Please put a " ✓ " in the appropriate box)

1. <i>A</i>	As a whole	, I feel that this publication is:	Strongly Agree	Agree	Neutral	Disagree	Strongly Disagree
		Informative					
		Comprehensive					
		Useful					
		Practical					
2. Does this publication enable you to understand more about the Statutory Requirements for the Modular Integrated Construction Projects?			Yes		No	No Co	omment
]
3. Have you made reference to this publication in your work?			Quite Often S		Sometimes	Ne	ver
4. To what extent have you incorporated the			Most		Some	None	
	recommendations of this publication in your work?]
5. Overall, how would you rate this publication?			Excellent	Very Good	Satisfactory	Fair	Poor
		nents and suggestions (please specify	and use s	separat	e sheets if ı	necessary	/).
Pers	sonal Parti	culars (optional):*					
Nam	ne:	Mr. / Mrs./ Ms./ Dr./ Prof./ Ir / Sr ^					
Com	npany:						
Tel:							
Addr	ress:						
E-ma	ail:						

* The personal data collected will be used only for this survey. Your data will be kept confidential and dealt with only by the Construction Industry Council.

^ Circle the appropriate option.

Please send this feedback form to:

MiC Department, Industry Development Division, CIC

Email: mic@cic.hk

Address: 38/F, COS Centre, 56 Tsun Yip Street, Kwun Tong, Hong Kong

Fax: (852) 2100 9090

Enquiries

Enquiries on this Reference Material may be made to the CIC Secretariat:

CIC Headquarters 38/F, COS Centre, 56 Tsun Yip Street, Kwun Tong, Kowloon

Tel : (852) 2100 9000
Fax : (852) 2100 9090
Email : enquiry@cic.hk
Website : www.cic.hk

2023 Construction Industry Council